

MATERIALS Permitted Build Domestic

"H" means host is responsible for acquiring the item; "D" means DomeGaia will bring the item.

NAME	CATEGORY	QTY	COMMENTS	LINK	APPROX PRICE
STRAIGHT LUMBER 2X4 8' (1.5" X 3.5" X 8')	LUMBER	50	H		\$161.00
PLYWOOD SHEETS 1/2"X 4' X 8'	LUMBER	14	H		\$17.00
PLYWOOD SHEETS 1/4"X 4' X 8'	LUMBER	1	H		\$17.00
PLYWOOD SHEETS 2.7mm X 4' X 8'	LUMBER	3	H		48
PLYWOOD SHEETS 5mm X 4' X 8'	LUMBER	5	H		83
EMT (ELECTRICAL METAL TUBING) 10' X 3/4"	METAL	20	H		110
ANGLE ALUMINUM 8' 1/16"x3/4"x3/4"	METAL	6	H		77
ANGLE ALUMINUM 8' 1/8"x1"x1"	METAL	4	H		128
12x1/8" STEEL ROD	METAL	6	H		46
METAL DIAMOND LATHE WIRE MESH 3' X 7'	METAL	1	H		9
4" HINGES	HARDWARE	32	H		115
BUNGEE CORDS 10"	HARDWARE	21	H		24
BRAIDED FISHING LINE 150LB TEST, 300 YARDS	MISC	1	H	https://www.amazon.com/PowerPro-Green-Line-150lb-21101500300E/dp/B000AJFS2	60
POLYURETHANE DECK SEALER 1.5 GALLONS	MISC	1	H		24
OUTDOOR PAINT 2 GAL	MISC	1	H		
PURE PORTLAND CEMENT 94LB BAGS	AIRCRETE	75	H	Depends largely on location. In Maui cost is \$20 per unit	1500
GALLON OF VEGGIE OIL	AIRCRETE	2	H	COSTCO	18
GALLONS OF FOAM CONCENTRATE (7TH GEN DISH LIQ)	AIRCRETE	6	H		112
FINE SAND ONE TON	AIRCRETE	1	H		50
LATEX BONDING AGENT GAL	AIRCRETE	7	H		3.35
ROOFING NAILS 2"	FASTENERS	100	H		190
PLEXIGLASS 1/4" X 4' X 8'	SKYLIGHT	1	H		12
GORILLA CONSTRUCTION ADHESIVE	GLUE	1	H		10
SILICONE FAST DRYING CALKING	GLUE	12	H		
WOOD GLUE	GLUE	2	H		
PIPE 2" X 10'	PVC	1	H		10
PIPE 3/4" X 10'	PVC	1	H		10
PIPE 1/2" X 10'	PVC	1	H		10
WOOD PLANK FOR DOOR 8' LONG 50 SQ FT.	DOOR	1	H		200
EMT 3/4" COUPLINGS	METAL	15	H		12
REINFORCING FABRIC ROLL	AIRCRETE	3	H	https://www.homedepot.com/p/BOEN-38-in-x-150-ft-Non-Adhesive-EIFS-Stucco-Mesh-EM	136
FIBER REINFORCEMENT	AIRCRETE	1	D	Domegaia brings these items, but they are to be paid for by the host. Approx. Cost \$350	20
TOGGLE CLAMPS	HARDWARE	16	D		24
HINGES FOR DOOR	HARDWARE	2	D		
COMPASS ARM MOUNT	HARDWARE	1	D		30
55 GAL BUCKET HANDLES	HARDWARE	4	D		10
WASHER .25" x 1.25"	FASTENERS	4	D		6
SS CAP NUTS .25"	FASTENERS	4	D		11
SS NUTS .25"	FASTENERS	12	D		4
SCREWS 3/4" PAN HEAD	FASTENERS	100	D		5
SCREWS 3/4" PAN HEAD SELF TAPPING	FASTENERS	100	D		5
SCREWS 1" (DOOR)	FASTENERS	100	D		6
SCREWS 1.25"	FASTENERS	100	D		
SCREWS 1.5"	FASTENERS	200	D		20
SCREWS 2"	FASTENERS	100	D		
SCREWS 2.5" (CUTTING JIG)	FASTENERS	100	D		20
SCREWS 3" (TUBING TO CROSSBARS)	FASTENERS	300	D		20
DECK 6" SCREWS (INNER WINDOW TO OUTER)	FASTENERS	12	D		15
BRAD NAILS (DOOR JAM) 1" AND 2"- ONE BOX OF EACH	FASTENERS	1	D		13
LAG BOLTS 1/2" x 3"	FASTENERS	12	D		0.75
CAP 2"	PVC	1	D		6
COUPLER 2"	PVC	1	D		6
REDUCER 2" TO 1"	PVC	1	D		6
T 3/4"	PVC	1	D		4
COUPLER SLIP TO FPT 3/4"	PVC	1	D		4
PLUG FLAT TOP MPT 3/4"	PVC	1	D		4
TEST PLUG 2"	PVC	1	D		9
ALUMINUM STRIP 10'	METAL	3	D		16
****END OF LIST****					

Total

\$3,457.10